

Checklist for Uploading of Tender on Central Public Procurement Portal (CPPP)

Sl. No.	Description	Value
1	Tender reference No.	6(1)2016-17/B&W
2	Tender type	Limited
3	Form of Contract	Work
4	No. of Bids	Single Bid
5	Tender Category	Works
6	Work/item title	Civil Works
7	Work/item Description	Repair & renovation of 2 Nos Gate in Farm Field Area
8	Tender value	Rs. 1,46,375/-
9	Bid Validity	Till 30/06/2021
10	Delivery/Completion Period	45 Days
11	Delivery Place/Location Detail	ICAR-IISWC, RC, DATIA
12 a	Pre Bid Meeting	No
12 b	Pre Bid Meeting Place	NA
12 c	Pre Bid Meeting Date & Time	NA
13	Bid Opening Place	ICAR-IISWC, RC, DATIA
14 a	Tender Inviting Officer	BD Kushwaha, TO & I/C (Store/Meteo.)
14 b	Department of Inviting office	ICAR-IISWC, RC, DATIA
15	EMD Exemption	Not Applicable
16 a	EMD Fee	N/A
16 b	EMD Amount	-
17 a	EMD Fee Payable to	Head, CSWCR&TI, RC, Datia
17 b	EMD Fee Payment Mode	Bank Draft
18	Tender Period	12 Days
19	Bid Publishing Date & Time	19/02/2021
20	Bid Submission Closing Date & Time	03/03/2021, 17.00 hrs
21	Bid Opening Date & Time	04/03/2021, 11.30 hrs
22	Person to seek clarification	Name –Bhagwan Das Kushwaha Desk Phone 9425791182 Email id: bdkush1970@gmail.com

Signature of PI / Indenter

C. Singh
19/02/2021



भाकृअनुप - भारतीय मृदा एवं जल संरक्षण संस्थान
ICAR-Indian Institute of Soil & Water Conservation
अनुसंधान केंद्र, दतिया, म.प्र., 475661
Research Centre-Datia, MP, 475661



क्रमांक.- 6(1)2016-17/B&W/ 594-601

दिनांक - 16/02/2021

19

सेवा में,

.....

.....

विषय:- फार्म/प्रक्षेत्र में दो गेटो की मरम्मत के सन्दर्भ में,

महोदय,

केंद्र पर फार्म/प्रक्षेत्र में दो गेटो की मरम्मत हेतु मय सामान एवं लेबर मजदूरी के संलग्न सारणी (अ) में उल्लेखित कार्य के लिए दरें आमंत्रित की जाती हैं निबंधन एवं शर्तें निम्नलिखित प्रकार से हैं।

निबंधन एवं शर्तें:-

1. दरें (कोटेसन) तारीख 03/03/2021, 17.00 बजे तक केन्द्राध्यक्ष, भारतीय मृदा एवं जल संरक्षण संस्थान, अनुसंधान केंद्र दतिया - 475661 को संबोधित करते हुए सील किये गए लिफाफे में (अपनी फर्म की सील का उपयोग किया जाए) इस केंद्र को रजिस्टर्ड पोस्ट/स्पीड पोस्ट से भेजी जानी चाहिए। तारीख 03/03/2021, 17.00 बजे के बाद प्राप्त होने वाली कुटेशनो पर विचार नहीं किया जायेगा। केंद्र द्वारा फर्म/ठेकेदार से व्यक्तिगत तौर पर दर कोटेसन प्राप्त नहीं की जावेगी।
2. केन्द्राध्यक्ष, भारतीय मृदा एवं जल संरक्षण संस्थान, अनुसंधान केंद्र दतिया - 475661 को कोटेसन को स्वीकार करने अथवा अस्वीकार करने का बिना कारण बताये पूर्ण अधिकार होगा।
3. कोटेसन प्रपत्र में अपने बैंक का खाता संख्या एवं बैंक का ब्रांच कोड, IFSC कोड तथा पैन कार्ड की फोटोकॉपी लगाना अनिवार्य है।
4. आपके द्वारा दी गयी कोटेसन मूल लैटर पद पर ही मान्य होगी। लैटर पैड की फोटोकॉपी पर मान्य नहीं होगी।
5. पंजीकृत ठेकेदार की कोटेसन ही मान्य होगी। पंजीकृत प्रमाणपत्र, GST रजिस्ट्रेशन प्रमाण पत्र कोटेसन के साथ देना होगा।
6. दर कोटेसनों को फर्मों को प्राधिकृत ठेकेदार/प्रतिनिधि की उपस्थिति में तारीख 04/03/2021 को प्रातः 11.30 बजे के पश्चात इस कार्यालय में खोला जायेगा।
7. सफल फर्म/ठेकेदार को केंद्र द्वारा कार्य आदेश दिए जाने पर कार्य की कुल लागत के अनुसार 3% परफॉरमेंस सिक्यूरिटी कार्य आरम्भ करने से पहले कार्यालय में जमा करवानी होगी। जमा की गयी

- परफॉरमेंस सिक्यूरिटी तथा EMD राशि पर कार्यालय द्वारा किसी भी प्रकार का ब्याज नहीं दिया जायेगा ।
परफॉरमेंस सिक्यूरिटी कार्य संतोषजनक एवं पूर्ण रूप से होने के पश्चात एक माह में लौटाया जायेगा ।
8. सभी फर्म/ठेकेदारों को सलाह दी जाती है कि वे फार्म/प्रक्षेत्र में दो गेटो की मरम्मत के सम्बन्धी कार्य की जानकारी केंद्र के सम्बंधित अधिकारी से भली-भाँति समझ लेवे ।
 9. फार्म/प्रक्षेत्र में दो गेटो की मरम्मत के कार्यों में इस्तेमाल होने वाले मटेरियल को इस्तेमाल करने से पूर्व सम्बंधित अधिकारी व प्रतिनिधि से सत्यापित करवाने के पश्चात ही उपयोग में लेना होगा । सामान औजार उपकरण इत्यादि स्वयं फर्म/ठेकेदारों को व्यवस्था करनी होगी, केंद्र द्वारा किसी भी प्रकार का मटेरियल व सामन, औजार उपलब्ध नहीं कराये जाएँगे ।
 10. उपरोक्त कार्य को सम्बंधित अधिकारी एवं प्रतिनिधि की उपस्थिति में बताई गयी निश्चित समयाविधि में पूर्ण करना होगा । कार्य संतोषजनक नहीं होने पर कार्य आदेश को किसी भी समय निरस्त किया जा सकता है जिसके नुकसान की जिम्मेदारी स्वयं फर्म/ठेकेदार की होगी । कार्य के दौरान किसी भी अप्रिय घटना के लिए केंद्र जिम्मेदार नहीं होगा ।
 11. केवल केंद्र के प्रमुख के विवेक से मात्र में वृद्धि या कमी की जा सकती है ।
 12. सफल ठेकेदार के पास CGST एवं GST, आधार नंबर का क्रमांक, तथा आयकर विभाग द्वारा प्रदात स्थायी लेखा क्रमांक पैन कार्ड होना आवश्यक है।
 13. केंद्र सरकार द्वारा स्वीकृत न्यूनतम दैनिक मजदूरी के अनुसार भुगतान सुनिश्चित करना फर्म/ठेकेदार के दायित्व होगा । अगर ठेकेदार द्वारा कार्य को अधूरा छोड़ दिया जाता है तो उसके द्वारा जमा की गयी परफॉरमेंस सिक्यूरिटी कार्यालय द्वारा जब्त कर ली जाएगी तथा उसके विरुद्ध कार्यवाही की जाएगी ।

संलग्न उपरोक्त अनुसार

Quotation for Repair and renovation of (2 Nos) at Research Centre Datia (MP) Table (A)

S No.	Description of Items	Unit	Qty	Rate Rs.	Amount Rs.
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge. In cement mortar	cum	2.80		
2	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	cum	10.37		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 40 mm nominal size)	cum	0.60		
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-II) : 4 graded stone aggregate 20 mm nominal size)	cum	3.70		
5	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size)	cum	2.21		
6	Centering and shuttering including strutting, propping etc. and removal of form for				
	Foundations, footings, bases of columns, etc. for mass concrete	sqm	8.64		

	Columns, Pillars, Piers, Abutments, Posts and Struts	sqm	22.08		
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	kg	360.00		
8	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	sqm	24.00		
9	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	kg	123.32		
	Locking arrangement hinges with pivot etc	(3 pair)	6.00		
10	Repairing of old gates:- welding/straightening work, making proper hinging, locking &strengthen arrangement and fixing at site	(2 pair)	4.00		

Signature.....

Name

Address

.....

Elevation for all gates / Rough Sketch

